BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK:Construction of Building and Development of Govt. School and improvements in school Premises at Jakkuru village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
35	Providing and fixing factory made splendoor of solid core single leaf rigid composite polymer laminated sal wood. door shutter of required thickness. manufactured out of solid core door conforming to IS 2202 (Part-1) 1991. laminated with 0.8 mm thick polymer. termite. water resistant and fire retardant with superior gluing based on vacuum lamination technology and with various pre moulded design on both faces conforming to IS 6307-1985. using adhesive conforming to IS 4835-1979 and door shuters tested in conformation to IS 4020-1994. The finish of shutters will be TEADK/OAK/CEDAR/ROSE WOOD/ WALNUT. plain colurs WHITE IVORY/BEIGE/LIGHT GREY. Excluding cost of fixtures and inclusive of supply of shutters to respective work spot. with door shutter 35mm thick.	Sqm	44.16	4000.0	Rupees Four Thousand Only
36	PVC DOOR SHUTTER : Supply and fixing of door shuttersmade of rigid PVC extruded hollow section of 20mm x 200mm with the wall thickness of 1.0mm +/0.1mm equally divided into 4nos with tongue and groove locking arrangements. The shutter frame is made of 58x24 mm with the wall thickness of 1.5mm+/-0.15mm section metricut and joined at 4 corners with 125mmx225mm plastic brackets. The shutter shall be horizontally reinforced with 2nos of 8mm PVC rods. Teak wood battons shall be reinforced inside the door shutter during the fabrication of the door shutter at those points wherever the hardware is fixed on to the door shutter.	Sqm	18.90	1999.90	Rupees One Thousand Nine Hundred Ninety Nine and Ninety Paise Only
37	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick.weight 1.07kg/m: sides and top sections 1.3 mm. thick. weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm. wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m. shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick. weight 0.469 kg/m. the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.: providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length. joints mitredsubdividing the frame tenonned and rivetted. in the assembled frame.stiffened with end clips for corners. angles etc.. and fixed to the walls.lintels. floor beams/cills as the case may be. with necessary steelscrews. raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement mortar.(using aluminium section powdered coated to a minimum of 60-70 microns with exterior durable pure polyester grade powder o	Sqm	39.48	4000.00	Rupees Four Thousand Only
38	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats. or M.S. square rods. or combination of M.S. flats and square rods as per approved design. drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer. cost of materials. fixtures. labour and HOM of machinery complete as per specifications.	Kg	829.08	115.0	Rupees One Hundred Fifteen Only
39	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications.	Sqm	853.71	70.0	Rupees Seventy Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jalahalli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
40	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer).	Sqm	1110.44	100.0	Rupees One Hundred Only
41	Providing and finishing external walls in two coats over one coat of 100% acrylic silicon glazed primer with antifungal paint for top coat of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	951.78	150.00	Rupees One Hundred Fifty Only
42	Applying priming coat over new wood surface and/ or wood based surface after preparing the surface after throughlycleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, completeas per specifications	Sqm	188.19	70.0	Rupees Seventy Only
43	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood basedsurface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications.	Sqm	99.36	100.0	Rupees One Hundred Only
44	Providing and applying enamel metal paint two coats(excluding priming coat) over new steel or other metal surfacebrushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as perspecifications.	Sqm	88.83	100.0	Rupees One Hundred Only
45	Providing Ceramic tiles/Antiskid tiles of size 30x30cms of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications.	Sqm	118.59	1000.00	Rupees One Thousand Only
. 46	Providing and fixing Vitrified glazed tiles, of approved make, quality and colour of size 600x600x10mm thick fixed on bed of 12 thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc., complete as per specifications.	Sqm	280.80	1200.00	Rupees One Thousand Two Hundred Only
47	Providing and fixing Skirting of 300mm high using prepolished water cut/gang saw of 19mm thick grey granite 0.5mm wide chamfered width and depth and fixing in CM 1:4 of 20mm thick after chipping the walls etc., complete.	Mtr	148.23	800.00	Rupees Eight Hundred Only
48	Providing and fixing 20mm thick gang saw water cut sadarhalli grey granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing.minimum width of 1200 mm.	Sqm	42.50	2500.0	Rupees Two Thousand Five Hundred Only
49	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification.	Mtr	70.00	200.0	Rupees Two Hundred Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK:Construction of Building and Development of Govt. School and improvements in school Premises at Jaganalli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
50	Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.Colour glazed tiles 30x60 cms 6mm thick with border of size 30 x 10 cms.	Sqm	213.00	1000.00	Rupees One Thousand Only
51	Flooring with 25mm to 40mm thick polished tandur blue stone slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed on top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab. , including cost of materials, labour, curing, polishing complete as per specifications.	Sqm	398.52	1200.00	Rupees One Thousand Two Hundred Only
52	Providing and fixing 304 - grade stainless steel hand rails of 14-gauge pipes for Ramps or Staircase are made out of stainless steel hallowpipes, using 50mm dia for verticals @1.60 mtr c/c are fixed tot he ramps or steps by drilling with bolts and 100mm dia MS base plates 10mm gauge for fixing of Vertical pipes 4 - Nos anchor bolts & 40mm dia pipes are fixed horizontally for 2-rows top, one pipes are fixed with vertical pipes another one are fixed with elbows and 25mm dia pipes are fixed horizontally for 2-rows below top measure @ equal intervals including cutting, welding, bending wherever necessary with suitable caps @ tops, bottoms & corners finishing with mat / shining etc., complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment with all lead and lift, loading and unloading, transportation charges and all other incidental charges etc., complete as per specification and directions of the Engineer-in-charge of the work. Ramps or Staircase for physically challenged.S.R Page no 43.	Sqm	16.37	6000.00	Rupees Six Thousand Only
53	Providing and fixing of Door locking arrangements Fixtures	No	12.00	600.0	Rupees Six Hundred Only
54	Providing and fixing of Handles powder coated 150mm Fixtures	No	39.00	70.0	Rupees Seventy Only
55	Providing and fixing of Hinges 5" heavy duty Fixtures	No	72.00	50.0	Rupees Fifty Only
56	Providing and fixing of Hold fasts MS Fixtures	No	145.00	50.0	Rupees Fifty Only
57	Providing and fixing of Tower bolt 300mm long Fixtures	No	24.00	200.0	Rupees Two Hundred Only
58	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications.	Cum	13.91	400.0	Rupees Four Hundred Only
59	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. ii) Dismantling Brick / Tile work. A. In lime mortar.	Cum	61.94	270.0	Rupees Two Hundred Seventy Only

For K. DAMODAR & CO.